

**NOTICE TO BIDDERS**  
**ADDENDUM #1**  
**TOWNSHIP OF RANDOLPH, MORRIS COUNTY, NEW JERSEY**  
**CCM PUMP STATION PROJECT**  
**BID OPENING DATE – AUGUST 5, 2022, 11:00 A.M.**

NOTICE IS HEREBY GIVEN that sealed bids for the above-referenced project for the Township of Randolph will include an acknowledgement of ADDENDUM #1. The ACKNOWLEDGEMENT OF RECEIPT OF CHANGES TO BID DOCUMENTS FORM included in the bid specifications must be completed and returned with the bid package. The Addendum shall become part of the original specifications and is to be attached thereto.

This Addendum is being issued in response to a bidder's questions.

Q1. "Is there any analytical/environmental test results available on the existing soil and if not, how should we categorize the soil for disposal?"

A1: There are no analytical/environmental test results available for the existing soil. Soil categorization and disposal shall be the responsibility of the Contractor. Per specification 312110, dispose of all excess material off of the property of the Owner, in a lawful manner and at the Contractor's own expense.

Q2: "What are the flows of each of the 2 existing pipelines that enter the existing pump station?"

A2: The flow from the sewer main extending from the college is approximately 83 gpm (with a peak flow of 208 gpm). The flow from the sewer main extending from Route 10 is approximately 42 gpm (with a peak flow of 105 gpm). As noted on plan sheet G-002, connection to the proposed pump station shall be during off-peak days / hours.

Elizabeth Crescibene, RPPO, QPA  
Purchasing Agent